

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T 48NR38W	<u>A-8</u> ✓
	T 48NR39W	M-8
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

REMONUMENTATION

OCT 3 1997

COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

¼ Corner common to Sections 24 & 19, T48N R38 & 39W.

I, Earl W. Applekamp in a field survey on June 10, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor, July 11, 1847. Set Cedar Post.

ORIGINAL BEARING TREES:

7" Fir	S66°W	11.88 feet
18" Hemlock	N23°E	10.56 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Corner position is in a county blacktop road. A fence line runs East from the corner position. Corner was re-established by single proportionate measure and on line between opposite Section Corners North & South.

Research on file with the Ontonagon County Remonumentation Program Representative.

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE
 7-15-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"x12" rebar with a 3" stamped cap 1 1/2" below top of blacktop. I established a reference monument, a 2 1/2"x30" aluminum pipe with a 3" cap stamped to read: County Remonumentation, T48N R38W, R39W, R.M., ¼, S24, S19, 1997, P.S. 17610. I also established three other bearing trees and reference objects.

REF. MON.	S49°E	51.26'	6" White Birch	N49°W	47.35'
9" Scotch Pine	S57°W	30.75'	Power Pole	N26°E	68.53'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date June 18, 1997