

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ONTONAGON
 (County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>39W</u>	<u>C-7</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

**SURVEY &
 REMONUMENTATION**

MAY 22 1997

COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner common to Sections 17, 18, 19 & 20, T48N R39W.

I, Earl W. Applekamp, in a field survey on July 02, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Artemas Curtis, U.S. Deputy Surveyor, September 05, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

Hemlock 16" N75°W 16.50 feet
 Hemlock 14" S74°E 17.16 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. An old fence runs South and East from the apparent corner position. There is evidence of farming South and West of this position. This position is in conformance with the original field notes. Corner was re-established at this position.

Research on file with the Ontonagon County Remonumentation Program Representative.

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE
 8-14-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2½"x30" aluminum pipe with a ¾" cap stamped to read: County Remonumentation, T48N R39W, S17, S18, S19, S20, 1996, P.S. 17610. I established four bearing trees and reference objects.

7" W. Pine N73°W 39.38' 4" W. Pine S36°W 57.94'
 3" Red Pine N11°E 69.14' Steel sign post East .89'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date August 14, 1996