

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>39W</u>	<u>E-7</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

SURVEY & REMONUMENTATION

MAY 22 1997

COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner common to Sections 16, 17, 20 & 21, T48N R39W.

I, Earl W. Applekamp, in a field survey on July 30, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Artemas Curtis, U.S. Deputy Surveyor, September 17, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

Aspen 8" N36°E 21.78 feet
 Aspen 11" S32°W 8.58 feet

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE
 08-08-96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. A gravel road runs South from the Corner location. There was a survey line cut West from the apparent location 30 years ago and has been kept open by the present property owner. Corner was set at the intersection of the cut line and the centerline of the gravel road. This location is in conformance with the original GLO calls.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"x24" rebar with a 3 1/4" stamped cap 6" below the gravel road. I established a reference monument, a 2 1/4"x30" aluminum pipe with a 3 1/4" cap stamped to read: County Remonumentation, T48N R39W, R.M., S16, S17, S20, S21, 1996, 17610. In addition I established 3 bearing trees.

REF. MON. N89°-12'-39"W 24.66' - 8" Cedar N08°-33'-31"E 38.10'
 5" Cedar S41°-21'-49"W 48.83' - 8" Cedar S28°-05'-29"E 45.30'



Signed by Earl W. Applekamp Date August 5, 1996
 Surveyor's Michigan License No. 17610