

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T48N R39W	E-9
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

SURVEY &
 REMONUMENTATION

MAY 22 1997

COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner common to Sections 20, 21, 28 & 29, T48N R39W.

I, Earl W. Applekamp, in a field survey on July 30, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original Corner established by Artemas Curtis, U.S. Deputy Surveyor, on September 16, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

Cedar 14" N45°E 5.94 feet
 Cedar 14" S15°W 3.30 feet

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE 08-08-96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. A gravel county road runs North, South and East from the apparent corner location. Corner was set at the intersection of these roads using the GLO stream calls to position the corner. This location is the only logical location, as the land is occupied by homes in all four directions.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"X24" rebar with a 3 1/4" stamped cap 6" below the surface of the gravel road. I established a reference monument, a 2 1/4"X30" aluminum pipe with a 3 1/4" cap stamped to read: County Remonumentation, T48N R39W, R.M., S20, S21, S28, S29, 1996, P.S. 17610. I also established 3 other reference trees and objects.



Ref. Mon. N38°-26'-05"E 50.12' - 17" Red Pine N59°-34'-53"W 47.76'
 Twin 9" Maples N02°-45'-46"E 128.78' - P. Pole S45°-59'-02"W 49.18'

Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date August 5, 1996