

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48NR 39W</u>	<u>E-10</u>
	T <u> R</u>	<u> </u>
	T <u> R</u>	<u> </u>
	T <u> R</u>	<u> </u>
2. Property Controlling In Section	S <u> T</u> <u> R</u>	<u> </u>
	S <u> T</u> <u> R</u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> T</u> <u> R</u>	<u> </u>
	S <u> T</u> <u> R</u>	<u> </u>

**SURVEY &
 REMONUMENTATION**

MAY 22 1997

COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

$\frac{1}{4}$ Corner common to Sections 28 and 29, T48N R39W.

I, Earl W. Applekamp, in a field survey on July 30, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Artemas Curtis, U.S. Deputy Surveyor, September 15, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

W. Pine 9" N50°W 16.50 feet
 W. Pine 9" S40°E 9.90 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. At the apparent corner position there is evidence of a fence line running East. To the West there is a fence in good repair and a row of red pines (12"± in diameter). A gravel road runs North and South. Corner was established by single proportionate measurement between opposite section corners and in the centerline of the gravel road.

Research of file with the Ontonagon County Remonumentation Program Representative.

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE
 08-08-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"x24" rebar with a 3/4" stamped cap 6" below the gravel road surface. I established one reference monument, a 2 1/2"x30" aluminum pipe with a 3/4" cap stamped to read: County Remonumentation, T48N R39W, R.M., 1/4, S28, S29, 1996, P.S. 17610. I also established three other bearing trees and reference objects.

REF. MON. S85°-43'-03"E 30.07' - 12" Red Pine N87°-20'-14"W 33.86'
 P. Pole S28°-17'-44"E 64.95' - 20" Red Pine S32°-59'-55"W 58.60'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date August 7, 1996