

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T48N R 39W	F-7
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

SURVEY & REMONUMENTATION

MAY 22 1997

COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

$\frac{1}{4}$ Corner common to Sections 16 & 21, T48N R39W.

I, Earl W. Applekamp, in a field survey on August 08, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Artemas Curtis, U.S. Deputy Surveyor, September 14, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

Cedar 14" N60°E 5.28 feet
 Fir 7" S30°W 15.84 feet

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE

9-12-96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. An old fence was found running East and South from near the calculated corner position. This fence was mostly down and barely visible in most areas. There was a 1½" pipe in the ground 19 feet Southeast of the calculated corner position. No record of this pipe could be found. Corner was re-established by single proportionate measurement and on line between opposite section corners.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2½"x30" aluminum pipe with a 3¼" cap stamped to read: County Remonumentation, T48N R39W, $\frac{1}{4}$, S16, S21, 1996, P.S. 17610. I established four bearing trees and reference objects.

14" Twin Maples N09°-26'-25"E 13.98' - 8" Cedar S11°-30'-18"E 35.21'
 11" Cedar N78°-37'-47"E 49.59' - Steel Sign Post West 1.22'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date August 28, 1996