

SURVEY & REMONUMENTATION

APR 25 1995

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

B B
102. Gr.
102. Gr.

COMMISSION

For corners in

ONTONAGON
(County)

Located in:

Corner Code #

1. Public Land Survey	T	48	R	39	F-9
	T		R		
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		R
	S		T		R
3. Miscellaneous Property in Sec.	S		T		R
	S		T		R

Recorded October 19 1994
at 2:13 o'clock P. M. in
Liber 3 page 216
Julie Marley Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1/4 corner, Section 21 and 28, T48N R39W

I, Earl W. Applekamp a field surveyor on October 01, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Artemus Curtis, U.S. Deputy Surveyor on September 26, 1851. Set Hemlock post.
Cedar 10" N27°W 16 links (10.56 feet)
White Birch 14" S38°E 22 links (14.52 feet)
1965 Highway plans show corner marked with 1/2" iron rod and ties to 3 objects.

**ONTONAGON COUNTY
PEER APPROVED**

*Earl W. Applekamp
Ont. Co. Rep.*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron rod and two of the three ties used in 1965. I accepted this position as being true. It was used on several surveys. Corner is consistent with G.L.O. calls. I monumented the corner and updated accessories to State and County specifications as noted below.



Research on file with County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the 1/2" iron rod with a 2 1/2"x30" long split base monument with a 3/4" aluminum cap stamped; County Monumentation 1/4 S-21, S-28, T48N R39W; 1994; P.S. 17610. I established the following bearing trees and reference objects:

Steel Sign Post	N70°W	1.02 feet	4" Scotch Pine S75°E, 56.77 feet
Telephone Pole	S08°W	8.22 feet	6" Spruce N08°W, 19.10 feet

Signed by Earl W. Applekamp P.S.
Surveyor's Michigan License No. 17610

Date October 05, 1994