

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T48NR 39W	G-5
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

SURVEY &
 REMONUMENTATION

MAY 22 1997

COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner common to Sections 9, 10, 15 & 16, T48N R39W.

I, Earl W. Applekamp, in a field survey on Oct. 04, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Artemas Curtis, U.S. Deputy Surveyor, September 16, 1851. Set Spruce Post.

ORIGINAL BEARING TREES:

Spruce 8" N45°W 28.38 feet
 Aspen 10" S64°E 35.64 feet

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE
 10-16-96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Corner position falls in the center of U.S. Highway 45. It was in existence for a survey performed by E.W. Applekamp in 1967. Since that time highway reconstruction has destroyed evidence of it. I re-established it from the survey I performed in 1967. Corner location is in conformance with calls to streams on the original field notes.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 1/2"x4" bolt with a 7/8" head in the centerline of Highway US-45. I established two reference monuments which are 2 1/2"x30" split base aluminum pipes with a 3 1/4" cap stamped to read: County Remonumentation, T48N R39W, R.M., S9, S10, S15, S16, 1996, P.S. 17610. I also established two bearing trees.

REF. MON. N65°-45'-57"W 77.85' - 6" W. Pine S77°-37'-58"W 101.28'
 REF. MON. N49°-30'-51"E 79.83' - 14" Spruce S53°-57'-56"E 97.94'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date October 10, 1996