

**SURVEY & REMONUMENTATION**

DEC 1 6 1996

COMMISSION

JUDITH D. ROEHN  
 Ontonagon County  
 LC 4/ 69 JEM Fee: 9.00  
 06/10/96  
 15:38  
 Page 1 of 1

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T48N R39W	G-7
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling In Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Section Corner common to Sections 15, 16, 21 & 22, T48N R39W.

I, Earl W. Applekamp, in a field survey on May 06, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Artemas Curtis, U.S. Deputy Surveyor, September 21, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

White Pine 14" N40°W 2 links  
 White Pine 16" S20°E 21 links

PEER GROUP APPROVED  
*Earl W. Applekamp*  
 COUNTY PROFESSIONAL SURVEYOR  
 06-06-96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found, except stream calls. At the apparent corner position I found a 1/2" Iron Pin with a cap marked 16936 in a monument box in the centerline of U.S. Highway 45. This corner position has been in existence for 35 years. It has been used by several surveyors for doing surveys in the area. I accepted the corner and perpetuated it as shown below.

Research on file with the Ontonagon County Remonumentation Representative



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I left the 1/2" Iron Pin in the monument box in the centerline of U.S. Highway 45. I established two reference monuments which are 2 1/2" aluminum pipe with a 3 1/4" cap stamped to read: County Remonumentation, R.M., T48N R39W, S15, S16, S21, S22, 1996, P.S. 17610. I also established two other reference objects.

REF. MON. S88°-08'-31"W 55.13' P. Pole N27°-01'-19"W 138.30'  
 REF. MON. N67°-29'-20"E 63.33' P. Pole S31°-18'-41"E 99.86'

Signed by Earl W. Applekamp  
 Surveyor's Michigan License No. 17610

Date May 9, 1996