

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 48NR 39W	G-9
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___	_____
	S ___ T ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___	_____
	S ___ T ___	_____

**SURVEY &
 REMONUMENTATION**

MAY 22 1997

COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner common to Sections 21, 22, 27 & 28, T48N R39W.

I, Earl W. Applekamp, in a field survey on July 29, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Artemas Curtis, U.S. Deputy Surveyor, September 16, 1851. Set Hemlock Post.

ORIGINAL BEARING TREES:

Hemlock 14" N05°W 17.82 feet
 Maple 10" S25°W 17.16 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence remains. Corner position was found at the intersection of Michigan Highway M-28 and U.S. Highway 45. Corner is marked with a 5/8" iron rod in a monument box. This location will be left where it is and recorded.

Research on file with the Ontonagon County Remonumentation Program Representative.

Corner was re-established by MDOT, prior to 1970.

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE 9-12-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position there is a 5/8" iron rod in a monument box at the intersection of M-28 & US-45. I installed a 3/4" aluminum cap on the existing iron rod and stamped it as follows: County Remonumentation, T48N R39W, S21, S22, S27, S28, 1996, P.S. 17610. No reference monuments were set but four reference objects were established.

P. Pole N72°-55'-19"W 106.79' - P. Pole N35°-07'-42"E 45.30'
 P. Pole S33°-38'-01"W 46.60' - R.R. Spike in Blk. Top N24°-37'-33"E
 - 35.79 feet



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date August 17, 1996