

**SURVEY & REMONUMENTATION**

DEC 16 1996

COMMISSION

JUDITH D. ROEHM  
 Ontonagon County  
 LC 4/ 65 JEM Fee: 9.00  
 Page 1 of 1

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

|                                    |                   |               |
|------------------------------------|-------------------|---------------|
| <u>ONTONAGON</u><br>(County)       | Located In:       | Corner Code # |
| 1. Public Land Survey              | T <u>48NR 39W</u> | <u>G-10</u>   |
|                                    | T ___ R ___       | _____         |
|                                    | T ___ R ___       | _____         |
|                                    | T ___ R ___       | _____         |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____         |
|                                    | S ___ T ___ R ___ | _____         |
| 3. Miscellaneous Property in Sec.  | S ___ T ___ R ___ | _____         |
|                                    | S ___ T ___ R ___ | _____         |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

1/4 Corner common to Sections 27 & 28, T48N R39W.

I, Earl W. Applekamp, in a field survey on May 06, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    |   |    |   |    |   |    |   |    |   |    |   |    |   |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1  | A | B  | C | D  | E | F  | G | H  | I | J  | K | L  | M |
| 2  |   | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |
| 3  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 4  |   | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |
| 5  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 6  |   | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |
| 7  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 8  |   | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |
| 9  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 10 |   | 30 |   | 29 |   | 28 | ● | 27 |   | 26 |   | 25 |   |
| 11 |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 12 |   | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |
| 13 |   |    |   |    |   |    |   |    |   |    |   |    |   |

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Artemas Curtis, U.S. Deputy Surveyor, September 16, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

Spruce 20" N35°E 22 links  
 Fir 12" S46°W 21 links

PEER GROUP APPROVED  
Earl W. Applekamp  
 COUNTY REPRESENTATIVE  
 06-06-96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. At the corner position I found a 3/4" Iron Pin in a monument box in the center of the North bound lane of U.S. Highway 45. This corner has been in existence for approximately 35 years and has been used by several surveyors for describing land in the Bruce Crossing area. I accepted the location as the only logical position for the corner.

Research is on file with the Ontonagon County Remonumentation Representative

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I left the 3/4" Iron Pin in the monument box in U.S. Highway 45. I established two reference monuments which are 2 1/2" aluminum pipe with a 3 1/4" cap stamped to read: County Remonumentation, 1/4, R.M., S27, S28, 1996, P.S. 17610. I also established two other reference objects.

REF. MON. N66°-09'-20"W 62.33' P. Pole N26°-02'-02"E 138.25'  
 REF. MON. S50°-41'-17"E 61.11' P. Pole S50°-03'-01"W 103.15'



Signed by Earl W. Applekamp  
 Surveyor's Michigan License No. 17610

Date May 10, 1996