

OCT 3 0 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

ONTONAGON
(County)

Located In:

Corner Code #

JUDITH D. ROEHM 06/12/97
Ontonagon County 09:46
LC 4/274 JJT Feet 9.00
Page 1 of 1

- 1. Public Land Survey T48NR 39W I-3
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Section Corner common to Sections 2, 3, 10 & 11, T49N R38W.

I, Earl W. Applekamp in a field survey on May 29, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column I and row 3.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Artemas Curtis, U.S. Deputy Surveyor, September 1851. Set Wood Post.

ORIGINAL BEARING TREES:

- 10" W. Pine N69°E 9.90 feet
9" W. Pine S45°W 17.82 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Found an iron pin in the centerline of a four way road intersection. This location is in conformance with the original GLO notes. Farming is or has been going on in all four directions. I accepted the intersections of the four roads as being the only logical position for the corner.

Research on file with the Ontonagon County Remonumentation Program Representative.

PEER GROUP APPROVED

Earl W. Applekamp
COUNTY REPRESENTATIVE 6-10-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"x12" rebar with a 3" stamped cap 2" below the blacktop surface at the intersection of the centerline of four roads. I established a reference monument, a 2 1/2"x30" aluminum pipe with a 3" cap stamped to read: County Remonumentation, T48N R39W, R.M., S2, S3, S10, S11, 1997, P.S. 17610. I established three other reference objects.

- 4" Well Casing N45°W 35.47' - Telephone Pedestal S38°E 52.77'
Power Pole N44°E 45.80' - REF. MON. S42°W 60.93'



Signed by Earl W. Applekamp
Surveyor's Michigan License No. 17610

Date May 31, 1997