

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ONTONAGON (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 39W	I-5
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

**SURVEY &
 REMONUMENTATION**

MAY 22 1997

COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner common to Sections 10, 11, 14 & 15, T48N R39W.

I, Earl W. Applekamp, in a field survey on Sept. 30, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Artemas Curtis, U.S. Deputy Surveyor, September 23, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

Yellow Birch	10"	N45°W	11.22 feet
Cedar	12"	S10°E	18.48 feet

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE
 10-16-96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. The corner position is at the intersection of the 2 Mile and Larson Roads. This position is in agreement with the distances given in the original field notes. These roads have been in existence for 60-70 years. The corner was monumented at the intersection of the two roads. This is the only logical position for this corner.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"x11" rebar with a 3 1/4" stamped aluminum cap 2" below top of blacktop surface. I set a reference monument, a 2 1/2"x30" aluminum pipe with a 3 1/4" cap stamped to read: County Remonumentation, T48N R39W, R.M., S10, S11, S14, S15, 1996, P.S. 17610. I also established three other reference objects.

REF. MON.	N42°-19'-00"E	49.25'	- P. Pole	N42°-25'-24"W	44.38'
Power Pole	N07°-03'-32"W	243.44'	- P. Pole	S23°-50'-42"W	75.82'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date October 2, 1996