

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48NR 39W</u>	<u>I-6</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

**SURVEY &
 REMONUMENTATION**

MAY 22 1997

COMMERCIAL

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

$\frac{1}{4}$ Corner common to Sections 14 & 15, T48N R39W.

I, Earl W. Applekamp, in a field survey on 09-30, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3			2
3													
4	7						8			9			10
5													
6	18						17			16			15
7													
8	19						20			21			22
9													
10	30						29			28			27
11													
12	31						32			33			34
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Artemas Curtis, U.S. Deputy Surveyor, September 23, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

Hemlock 18" N41°W 28.38 feet
 Y. Birch 12" S16°E 3.96 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Corner was re-established by single proportionate measurement between opposite section corners and in the center-line of a gravel road. (Larson Road)

Research on file with the Ontonagon County Remonumentation Program Representative.

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE 10-16-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"x24" rebar with a 3 1/4" stamped aluminum cap 6" below the surface of the gravel road. I established a reference monument, a 2 1/2"x30" split base aluminum pipe with a 3 1/4" cap stamped to read: County Remonumentation, T48N R39W, R.M., 1/4, S14, S15, 1996, P.S. 17610. I also established three other reference objects.

REF. MON. S89°-35'-53"E 40.63' - 4" Spruce N42°-08'-30"W 71.59'
 4" Aspen N47°-07'-56"E 109.53' - P. Pole S15°-44'-30"W 117.95'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date October 8, 1996

207