

JUDITH D. ROEHL  
 Ontonagon County  
 LC 4/296 JDR Fee: 9.00  
 07/17/97  
 15:00  
 Page 1 of 1

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T48NR39W	J-7
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

GENERAL INVESTIGATION  
 OCT 29 1997  
 COMMISSION  
 Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

$\frac{1}{4}$  Corner common to Sections 14 & 23, T48N R39W.  
 I, Earl W. Applekamp, in a field survey on June 13, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 Original corner established by Artemas Curtis, U.S. Deputy Surveyor, September 19, 1851. Set Wood Post.

ORIGINAL BEARING TREES:  
 14" Cedar N55°W 3.96 feet  
 15" Hemlock S65°E 6.60 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 No original evidence was found. A county gravel road runs East and West at corner position. Corner was re-established by single proportionate measure between opposite section corners East & West and in the center-line of the gravel road. Corner position is in conformance with a stream call 85.8 feet West.

Research on file with the Ontonagon County Remonumentation Program Representative.

PEER GROUP APPROVED  
Earl W. Applekamp  
 COUNTY REPRESENTATIVE  
 7-15-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 At the corner position I set a 5/8"X12" rebar with a 3" stamped cap 6" below top of gravel road. I established a reference monument, a 2 1/2"X30" aluminum pipe with a 3" cap stamped to read: County Remonumentation, T48N R39W, R.M.,  $\frac{1}{4}$ , S14, S23, 1997, P.S. 17610. I also established 3 bearing trees.

REF. MON.	N22°E	37.14 feet - 6" Aspen	S41°W	46.96 feet
6" Aspen	S41°E	44.02 feet - 4" White Pine	N20°W	32.38 feet



Signed by Earl W. Applekamp  
 Surveyor's Michigan License No. 17610

Date June 17, 1997