

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ONTONAGON (County)	Located In:	Corner Code #
1. Public Land Survey	T48N R39W	J-9
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

OFFICE of
REMONUMENTATION
 OCT 8 0 1997
 COMMISSION
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

1/2 Corner common to Sections 23 & 26, T48N R39W.

I, Earl W. Applekamp, in a field survey on June 20, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Artemas Curtis, U.S. Deputy Surveyor, September 20, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

15" Hemlock N28°W 13.20 feet
 11" Hemlock S05°E 16.50 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Corner falls in Michigan State Highway M-28. Highway drawings do not identify the 1/4 Corner. A county road runs North and South from the apparent corner position. A survey by Victor Arcand, RLS, dated December 5, 1964 set iron pins in a parcel of land in the NE Corner of the NW 1/4. The survey map identifies a R.R. Spike in the blacktop. This road has been re-surfaced since this date. I re-established the 1/4 Corner using iron pins set by Arcand.

Research on file with the Ontonagon County Remonumentation Program Representative.

PEER GROUP REPRESENTATIVE
Earl W. Applekamp
 COUNTY REPRESENTATIVE
 8-13-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 1/2"X5" iron pin in the centerline of Highway M-28. I established two reference monuments which are 2 1/2"X30" aluminum pipes with a 3" cap stamped to read: County Remonumentation, T48N R39W, R.M., 1/4, S23, S26, 1997, P.S. 17610. I also established two other reference objects.

REF. MON. S26°-37'-41"W 88.01' - P. Pole S44°-32'-38"W 90.37'
 REF. MON. S41°-48'-24"E 103.95' - P. Pole N08°-39'-55"E 138.36'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date July 29, 1997