

REMIC

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

OCT 3 0 1997

For corners in

ONTONAGON (County)	Located In:	Corner Code #
1. Public Land Survey	T48NR 39W	K-3
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling In Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

COMMISSIONER

JUDITH D. ROEHN  
Ontonagon County  
LC 4/266 JJT Fee: 9.00  
Page 1 of 1

06/12/97  
09:21

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Corner common to Sections 1, 2, 11, & 12, T48N R39W.

I, Earl W. Applekamp, in a field survey on May 21, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Artmas Curtis, U.S. Deputy Surveyor, September 1851, set Wood Post.

ORIGINAL BEARING TREES:

Hemlock 7" N65°E 17.82 feet - Hemlock 10" S35°W 25.74 feet  
Champion Timberlands (Low & Burkland) indicate they set a point in a dirt road from the stump of the original 10" Hemlock bearing tree. From this point they set a CFI Post, S67°E, 11.55 feet and a CFI Poster on a 5" Hard Maple, S78°E, 8.58 feet.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. No evidence of the Champion Timberlands restoration could be found, except for the dirt road. A dozer had done some work in the area. A local resident, Reino Alanen, a retired Dept. of Transportation surveyor showed Joe Domitrovich, P.S., where he remembered the position of the corner as Champion had reset it. A blue line runs East, West and North from the apparent position. I re-established the corner in the center-line of the dirt road East-West and on a blue line running North. This is the position that Alanen remembered it to be. This position is in conformance with original calls in four directions.  
Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 1/2" X 30" aluminum pipe with a 3" cap stamped to read: County Remonumentation, T48N R39W, S1, S2, S11, S12, 1997, P.S. 17610. I established three bearing trees and one reference object.

8" Maple N88°-30'W 81.98' - 8" Maple S62°-05'E 35.91'  
8" Maple N00°-35'E 44.15' - Steel Sign Post, East 1.00'

ONTONAGON COUNTY  
FIELD APPROVED  
*Earl Applekamp, C.S.*  
June 10, 1997



Signed by Earl W. Applekamp  
Surveyor's Michigan License No. 17610

Date May 23, 1997