

OCT 3 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ONTONAGON (County)	Located In:	Corner Code #
1. Public Land Survey	T48N R39W	K-6
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

JUDITH D. ROEHM 06/12/97
 Ontonagon County 09:45
 LC 4-272 JJT Feet 9.00
 Page 1 of 1

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Quarter Corner common to Sections 13 & 14, T48N R39W.

I, Earl W. Applekamp, in a field survey on May 16, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Artemas Curtis, U.S. Deputy Surveyor, September 1851. Set Wood Post.

ORIGINAL BEARING TREES:

Cedar	8"	N60°E	11.22 feet
W. Pine	16"	S55°W	7.26 feet

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE 6-10-97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Apparent corner position is in a graveled county road. A fence line runs East & West from the apparent position. The fence lines are 4 feet apart, measured North and South. I re-established the corner in the centerline of the gravel road and equal distance between the fence lines running East and West.

Research on file with the Ontonagon County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"X24" rebar with a 3" stamped cap 6" below top of gravel road. I established a reference monument, a 2 1/2"X30" aluminum pipe with a 3" cap stamped to read: County Remonumentation, T48N R39W, R.M., S13, S14, 1997, P.S. 17610. I established three other witness trees.

REF.MON.	S75°-15'W	30.33 feet - 6" Aspen	N71°-07'E	44.39 feet
8" Aspen	N49°-57'W	54.30 feet - 8" W. Pine	S35°43'E	70.51 feet



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date May 26, 1997