

RECORDED

OCT 3 01997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>39W</u>	<u>K-7</u>
	T___R___	_____
	T___R___	_____
	T___R___	_____
2. Property Controlling in Section	S___T___R___	_____
	S___T___R___	_____
3. Miscellaneous Property in Sec.	S___T___R___	_____
	S___T___R___	_____

JUDITH D. FOENE 06/12/97
 Ontonagon County 09:48
 LC 4/277 JJI Feet: 9.00
 Page 1 of 1

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner common to Sections 13, 14, 23, & 24, T48N R39W.

I, Earl W. Applekamp, in a field survey on May 16, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Artemas Curtis, U.S. Deputy Surveyor, September 1851. Set Wood Post.

ORIGINAL BEARING TREES:

White Pine 18" N60°E 22.44 feet
 Spruce 7" S70°W 5.94 feet

PEER GROUP APPROVAL
Earl W. Applekamp
 COUNTY REPRESENTATIVE
 6-10-97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Corner position is the intersection of two county roads. Area has and is being extensively farmed. I found an iron pin at the intersection of the centerlines of the two roads. Calls from the original field notes to corners in four directions are in conformance. I re-established the corner at the intersection of the two roads as being the only logical position for the corner.

Research on file with the Ontonagon County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"x24" rebar with a stamped cap 6" below top of gravel road. I established a reference monument, a 2 1/2"x30" aluminum pipe with a 3" cap stamped to read: County Remonumentation, T48N R39W, R.M., S13, S14, S23, S24, 1997, P.S. 17610. I also established three other reference objects.

Power Pole N50°W 47.28' - 3" Aspen S52°E 74.85'
 Stop Sign N58°E 45.86' - REF. MON. S49°W 57.02'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date May 27, 1997