

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ONTONAGON (County)	Located In:	Corner Code #
1. Public Land Survey	T48N R39W	K-10
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

REMONUMENTATION  
 OCT 30 1997  
 COMMISSION  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

1/4 Corner common to Section 25 & 26, T48N R39W.

I, Earl W. Applekamp, in a field survey on July 24, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26	●	25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Artemas Curtis, U.S. Deputy Surveyor, September 21, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

7" Sugar Maple	N67°W	22.44 feet
15" Sugar Maple	S40°E	12.54 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. There is a good dirt road running from the corner common to 23, 24, 25 & 26 to the 1/4 corner position. At this point there is the remains of a fence running 29 feet West and then North. Selective logging has been done Southeast of the corner position. I re-established the corner by single proportionate measure and on line with opposite section corners.

Research on file with the Ontonagon County Remonumentation Program Representative.

PEER GROUP APPROVED  
*Earl W. Applekamp*  
 COUNTY REPRESENTATIVE  
 8-13-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 1/2" x 30" aluminum pipe with a 3" cap stamped to read: County Remonumentation, T48N R39W, 1/4, S25, S26, 1997, P.S. 17610. I established three bearing trees and a reference object.

6" Hard Maple	S47°W	37.99'	-	8" Oak	N85°E	30.17'
7" Ash	N22°E	53.73'	-	Steel Sign Post		0.90'



Signed by Earl W. Applekamp  
 Surveyor's Michigan License No. 17610

Date July 28, 1997