

OCT 3 0 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSIONER

For corners in

ONTONAGON
(County)

Located In:

Corner Code #

- 1. Public Land Survey T48NR 39W L-5
 T ___ R ___
 T ___ R ___
 T ___ R ___
- 2. Property Controlling S ___ T ___ R ___
 In Section S ___ T ___ R ___
- 3. Miscellaneous S ___ T ___ R ___
 Property in Sec. S ___ T ___ R ___

JUDITH D. ROEHM 06/12/97
 Ontonagon County 09:42
 LC 4/269 JJT Fee: 9.00
 Page 1 of 1

JUDITH D. ROEHM 06/12/97
 Ontonagon County 09:42
 LC **Register of Deeds Stamp & File Number**
 Page 1 of 1

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Quarter Corner common to Sections 12 & 13, T48N R39W.

I, Earl W. Applekamp, in a field survey on May 30, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 Original corner established by Artemas Curtis, U.S. Deputy Surveyor, September 22, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

- 6" Black Ash N36°W 16.50 feet
- 10" Cedar S60°E 15.18 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 No original evidence was found. Corner position is in a blacktop road. Farming is being done in three directions. Corner was re-established at equal distance between opposite Section Corners and in the center-line of the blacktop county road.

Research on file with the Ontonagon County Remonumentation Program Representative.

PEER GROUP APPROVED
Earl W. Applekamp
COUNTY REPRESENTATIVE
 6-10-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 At the corner position I set a 5/8"x12" rebar, with a 3" stamped cap 2" below top of blacktop. I set a reference monument, a 2 1/2"x30" aluminum pipe with a 3" cap stamped to read: County Remonumentation, T48N, R39W, R.M., 1/4, S12, S13, 1997, P.S. 17610. I established three other witness objects.

- REF. MON. N17°E 40.25 feet - 5" Spruce S03°W 46.69 feet
- 5" Aspen N58°E 102.10 feet - Power Pole N76°W 128.35 feet



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date June 7, 1997