

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ONTONAGON (County)	Located In:	Corner Code #
1. Public Land Survey	T48NR 39W	L-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

REGISTER OF DEEDS
REMONUMENTATION
 OCT 30 1997
 COMMISSION
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

1/4 Corner common to Sections 25 & 36, T48N R39W.

I, Earl W. Applekamp, in a field survey on June 21, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Artemas Curtis, U.S. Deputy Surveyor, September 21, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

10" Hemlock N25°W 9.24 feet
 15" Sugar Maple S20°E 14.52 feet

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE
 8-13-97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


No original evidence was found. Corner position is in a county gravel road. A County road running North does not agree with a split of the Section. Original GLO notes has the distance 42 feet long. An old resident, Reino Nurkkala indicated this road has always been the 1/4 line. There were corner ties used by John Garske P.S. & Earl Applekamp P.S. but the actual corner stake has been destroyed by road improvements. The intersection of the "T" road has been used as the property division for 70 Plus years. A woods-field line South is in conformance to the "T" road. I re-established the corner at the intersection of the "T" road.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"x12" rebar with a 3" stamped cap 6" below the gravel road surface. I established a reference monument, which is a 2 1/2"x30" aluminum pipe with a 3" cap stamped to read: County Remonumentation, T48N R39W, R.M., 1/4, S25, S36, 1997, P.S. 17610. I also established 3 other reference objects.

REF. MON. S20°-23'-29"E 65.21' - 11" Red Pine N62°-55'-00"W 116.11'
 P. Pole S58°-15'-35"W 88.86' - 11" Hard Maple N50°-09'-26"E 62.84'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date July 29, 1997