

OCT 8 9 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

06-12-97

09:48

LC 4-276 JJT Fee: 9.00
Page 1 of 1

For corners in

ONTONAGON
(County)

Located In: Corner Code #

- 1. Public Land Survey

T 48NR 39W	M-5 ✓
T 48NR 38W	A-5
T ___ R ___	_____
T ___ R ___	_____
- 2. Property Controlling in Section

S ___ T ___ R ___	_____
S ___ T ___ R ___	_____
- 3. Miscellaneous Property in Sec.

S ___ T ___ R ___	_____
S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Section Corner common to Section 12 & 13, T48N R39W and Section 7 & 18, T48N R38W.

I, Earl W. Applekamp, in a field survey on May 29, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor, July 1847. Set Cedar Post.

- 12" Fir S83°W 5.28 feet
- 10" Hemlock N77°E 20.46 feet

PEER GROUP APPROVED
Earl W. Applekamp
COUNTY REPRESENTATIVE
6-10-97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Corner position falls at the intersection of roads running North, South and West. A dirt road runs East. Area has been farmed extensively. I found an iron pin at the intersection of the "T" road. This position was accepted as the only logical position for the corner.

Research on file with the Ontonagon County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I raised the iron pin with a 5/8"X12" rebar with a 3" stamped cap set 2" below the top of the blacktop road. I established a reference monument, a 2 1/2"X30" aluminum pipe with a 3" cap stamped to read: County Remonumentation, T48N, R38W, R39W, R.M., S12, S13, S7, S18, 1997, P.S. 17610. I established three other reference objects.

- REF. MON. N49°W 56.00 feet - 15" Apple Tree S33°E 73.19 feet
- Power Pole N44°E 45.84 feet - 17" Spruce S45°W 70.39 feet



Signed by Earl W. Applekamp
Surveyor's Michigan License No. 17610

Date May 30, 1997