

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

OCT 30 1997

For corners in

COMMISSION

Table with columns: Located In, Corner Code #. Includes entries for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

JUDITH D. ROEHN
Ontonagon County
LC 4/268 JJT Feet: 9.00
Page 1 of 1

JUDITH D. ROEHN
Ontonagon County
Register of Deeds Stamp & File Number

Page 1 of 1

4. Lot No. , Recorded Plat
5. Private Claims

Section Corner common to 13, 24, T48N R39W & 18 & 19, T48N R38W.

I, Earl W. Applekamp, in a field survey on May 16, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Contains numerical data for survey points.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor, July 10, 1847. Set Cedar Post.

ORIGINAL BEARING TREES:

Hemlock 14" S80.5°E 12.54 feet
Spruce 12" N45°W 12.54 feet

PEER GROUP APPROVED
Earl W. Applekamp
COUNTY REPRESENTATIVE

6-10-97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. The area is being farmed. A blacktop road runs N & S and a gravel road runs E & W from the apparent corner position. A P.K. nail was found at the intersection of the two roads. This position is in conformance with corners N, S, & W. I re-established the corner at the intersection of the roads, being the only logical placement for the corner.

Research on file with the Ontonagon County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"X24" rebar with a 3" stamped cap, 2" below top of blacktop at the intersection of the two county roads. I set a reference monument, a 2 1/2"X30" aluminum pipe with a 3" cap stamped to read: County Remonumentation, T48N, R39W, R38W, S13, S18, S24, S19, R.M., 1997, P.S. 17610. I also established 3 other reference objects.



STOP Sign S63°W 41.06' - REF. MON. N53°E 49.51'
8" Scotch Pine N32°W 87.45' - Power Pole S34°E 61.17'

Signed by Earl W. Applekamp
Surveyor's Michigan License No. 17610

Date May 24, 1997