

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T48N R38W	A-9
	T48N R39W	M-9 ✓
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

REGISTERED
 REMONUMENTATION
 OCT 3 0 1997
 COMMISSION
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner common to Sections 19 & 30, T48N R38W and Sections 24 & 25, T48N R39W.

I, Earl W. Applekamp, in a field survey on June 10, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, Deputy Surveyor, July 12, 1847. Set Cedar Post.

ORIGINAL BEARING TREES:

10" Cedar S79 $\frac{1}{2}$ °W 8.58 feet
 16" Cedar N13°E 14.52 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. An iron pin was found in the center-line of four county roads. This iron pin has been used for numerous surveys in the area. It is the only logical position for the corner. I accepted the iron pin as the true position of the corner and monumented it as shown below.

Research on file with the Ontonagon County Remonumentation Program Representative.

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE
 7-15-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I raised the iron pin with a 5/8"X12" rebar and set a 3" stamped cap 2" below top of blacktop. I established a reference monument, a 2 $\frac{1}{2}$ "X30" aluminum pipe with a 3" cap stamped to read: County Remonumentation, T48N, R38W, R39W, R.M., S24, S19, S25, S30, 1997, P.S. 17610. I also established three other reference objects.

REF. MON. N44°W 61.16' Power Pole S51°E 37.81'
 Power Pole N14°E 120.68' Light Pole S13°W 107.66'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date June 20, 1997