

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T 48NR 38W T 48NR 39W T ___ R ___ T ___ R ___	A-10 M-10 ✓
2. Property Controlling in Section	S ___ T ___ R ___ S ___ T ___ R ___	_____ _____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___ S ___ T ___ R ___	_____ _____

REMONUMENTATION
 007 3 01997
 COMMISSION
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

1/4 Corner common to Section 30, T48N R38W and Section 25, T48N R39W.
 I, Earl W. Applekamp, in a field survey on June 20, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		19		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10	●	30		29		28		27		26		25	●
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor, July 12, 1847. Set Hemlock Post.

ORIGINAL BEARING TREES:

7" Fir S62 1/2° E 11.22 feet
 10" Hemlock N44° W 23.10 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. A county blacktop road runs North & South from the corner position. There was a P.K. in the blacktop. This was within an inch of the split of the section. Four surveys were performed North & South from this point. I re-established the corner by single proportionate measure and on line between opposite section corners.

Research on file with the Ontonagon County Remonumentation Program Representative.

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE
 7-15-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"X8" rebar with a 3" stamped cap 1" below top of blacktop. I established a reference monument, a 2 1/2"X30" aluminum pipe with a 3" cap stamped to read: County Remonumentation, T48N R38W, R39W, R.M., 1/4, S25, S30, 1997, P.S. 17610. I also established three other reference objects.

REF. MON. S51°E 55.28' Guy Pole N19°W 93.26'
 Power Pole S08°E 134.24' Power Pole N18°E 65.40'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date June 23, 1997