

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T48N R 40W T48N R 41W T ___ R ___ T ___ R ___	<u>A-8</u> M-8 _____ _____
2. Property Controlling In Section	S ___ T ___ R ___ S ___ T ___ R ___	_____ _____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___ S ___ T ___ R ___	_____ _____

SURVEY &
REMONUMENTATION

JAN 11 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

1/4 Corner common to Sections 19 & 24, T48N R40W & R41W.

I, Earl W. Applekamp, in a field survey on June 18, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William A. Burt, U.S. Deputy Surveyor, July 14, 1847. Set Maple Post.

ORIGINAL BEARING TREES:

10" Fir	N41°E	19.80 feet
30" White Pine	S45°W	3.96 feet

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY SURVEYOR
 7-22-98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Corner position falls in a county road. Corner was re-established by single proportionate measure between opposite section corners and in the centerline of the County Road.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"x12" rebar with a 3" cap, stamped to read: County Remonumentation, T48N, R40W, R41W, 1/4, S19, S24, 1998, P.S. 17610. I established a reference monument, a 2 1/2"x30" aluminum pipe with a 3" cap stamped as above. I also established 3 bearing trees.

REF. MON.	N88°-28'-38"W	30.75'	- Nail in 7" Aspen	S70°E	37.49'
	N28°W	67.05'	- Nail in 6" Aspen	S45°W	52.92'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date July 15, 1998