

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T48N R 40W	E-6
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

SIXTEEN
 SECTION

JAN 11 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

$\frac{1}{4}$ Corner common to Sections 16 & 17, T48N R40W.

I, Earl W. Applekamp, in a field survey on August 7, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17	●	16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Wells Burt, U.S. Deputy Surveyor, June 2, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

36" White Pine S23°E 8.58 feet
 10" Cedar N85°E 10.56 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence or subsequent restoration evidence was found. Corner position is in a graveled County Road. I re-established the corner by single proportionate measure and on line between opposite corners in the center-line of the North Fair Oaks Road.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"X21" rebar with a 3" stamped cap 6" below top of the gravel road. I established a reference monument, a 2 1/2"X30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T48N R40W, R.M., $\frac{1}{4}$, S16, S17, 1998, P.S. 17610. I also established 3 other bearing objects.

REF. MON. S89°-18'-41"E 32.64' - Nail in P. Pole S08°W 233.29'
 Nail in 7" Maple N55°E 56.61' - Nail in P. Pole N16°W 118.62'

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE
 8-19-98



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date August 17, 1998