

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T48N R 40W	E-8
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

**SURVEY & REMONUMENTATION**

MAY 22 1997

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner common to Sections 20 & 21, T48N R40W.

I, Earl W. Applekamp, in a field survey on June 13, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Wells Burt, U.S. Deputy Surveyor, June 4, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

Y. Birch 12" S74°E 5.94 feet  
 Y. Birch 8" N47°E 20.46 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. At the apparent corner position there is a county road running North & South and fields East & West. There is a fence, rock piles & trees running East 20 feet South of the calculated corner position. Roy Paajanen, 72 years old and a lifelong occupant of the farm at this corner, said that the fence was placed there because a road ran East from the  $\frac{1}{4}$  position to a farm  $\frac{1}{2}$  mile East. This road is still evident. Corner was re-established by single proportionate measurement and in the centerline of the existing road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"x24" rebar with a 3/4" stamped cap 4" below the top of the gravel road. I established one reference monument, a 2 1/2"x30" aluminum pipe with a 3/4" cap stamped to read: County Remonumentation, T48N R40W, R.M., 1/4, S20, S21, 1996, P.S. 17610. I also established three other bearing trees and reference objects.

REF. MON. N86°-36'-28"E 28.68' - P. Pole N36°-18'-05"E 56.56'  
 4" Basswood N32°-10'-07"W 39.56' - 4" Spruce S19°-29'-27"E 71.61'

PEER GROUP APPROVED

Earl W. Applekamp  
 COUNTY REPRESENTATIVE  
 9-12-96



Signed by Earl W. Applekamp  
 Surveyor's Michigan License No. 17610

Date August 27, 1996