

SURVEY & REMONUMENTATION

DEC 16 1996

COMMISSION

JUDITH D. ROEHM
 Ontonagon County
 LC 4/46 JEM Fee: 9.00
 Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>40W</u>	<u>E-9</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner common to Sections 20, 21, 28 & 29, T48N R40W.

I, Earl W. Applekamp, in a field survey on April 24 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by J. Wells Burt, U.S. Deputy Surveyor, June 1851. Set Wood Post.

ORIGINAL BEARING TREES:

Sugar 20" S52°E 15 links
 Birch 12" N55°E 29 links

PEER GROUP APPROVED
Earl W. Applekamp 5-07-96
 COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Corner position is located at the intersection of two County Roads which have been there since 1900+. Location is consistent with original calls and surveys performed in the area. Corner was re-established using evidence from highway drawings, private surveys and original field notes.

Research on file with County Remonumentation Representative.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

At the corner position I set a 3/4"x15" aluminum rod with a 3 1/4" cap set 1 1/2" below top of blacktop road and stamped to read: County Remonumentation, S20, S21, S28, S29, T48N R40W, 1996, P.S. 17610. I established one reference monument a 2 1/2"x30" aluminum pipe with a 3 1/4" stamped cap and three reference objects.

REF. MON. S43°-45'-30"W 53.64' REA P. Pole N10°-05'-42"E 177.70'
 REA P. Pole S48°-26'-57"E 41.21' 36" Twin Oak N66°-54'-45"W 140.91'

Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date April 29, 1996