SURVEY & REMONUMENTATION

APR 2 9 1996

JUDITH D. ROEHM Untonason County 3/ 310 JEM

09/22/95

Foo!

08:42

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Page I of 1

	((ONTONAGON County)	Located In:	Corner Code #
1.	Public Land	d Survey	T 48 R 40 T 47 R	E-13 v
2.	Property Co	ontrolling	T R S T R S T R	
3.	Miscellaned Property in		S T R S T R	


Register of Deeds Stamp & File Number

__, Recorded Plat__ 5. Private Claims __

Section Corner common to S32 & 33, T48N R40W, S4 & S5, T47N R40W.

I, Ear1 W. Applekamp, in a field survey on August 03, 19 95 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current

manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:



Description of original monument and accessories and/or subsequent restoration:

Original corner established by Wills Burt, U.S. Deputy Surveyor, June 1857. Set Cedar Post.

ORIGINAL BEARING TREES:

40" White Pine N59°E 55 links (36.30 feet) 18" Cedar N49°W 41 links (27.06 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. There is a County gravel road running $N \sim S$ and another running West from the apparent corner. A distance of 5266.84 feet was measured from the centerline of the "T" roadway. This location is the most logical point for the corner. I accepted the centerline of the two roads and set a monument described in "C" below.

> PEER GROUP APPROVED Kamp 9-20-95 COUNTY

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 3/4"x24" aluminum rod with a 3½" aluminum cap 4" below the gravel surface. The cap is stamped to read: COUNTY

REMONUMENTATION, T48N R40W, T47N R40W, S32, S33, S4, S5, 1995, P.S. 17610

APPLEKAMP

APPLEKAMP

6" Aspen N23°W 7" Aspen S19°E

165.31 feet 112,15 feet REA Power Pole N42°E Steel Sign Post East

Date

EARL W.
APPLEKAMP
PROFESSIONAL
SURVEYOR
NO.
17610

Surveyor's Michigan License No.

September 20, 1995

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971 REVISED MAY 14, 1975 REVISED JAN., 1983