

SURVEY & REMONUMENTATION

DEC 16 1996

COMMISSION

JUDITH D. ROEHL
Ontonagon County
LC 4/88 JEM Feet 9.00
07/11/96 08:41
Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T47N R40W T48N R40W	<u>F-1</u> <u>F-13</u>
2. Property Controlling in Section	S T R S T R	
3. Miscellaneous Property in Sec.	S T R S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
	6		5		4		3		2			
	7		8		9		10		11		12	
	18		17		16		15		14		13	
	19		20		21		22		23		24	
	30		29		28		27		26		25	
	31		32		33		34		35		36	

1/4 Corner common to Sections 4 & 33, T47N R40W & T48N R40W.

Earl W. Applekamp, in a field survey on May 29, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by John Burt, U.S. Deputy Surveyor, July 13, 1850. Set Hemlock Post.

ORIGINAL BEARING TREES:

Hemlock 4" N60°E 32 links
Fir 9" N57°W 9 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO original evidence was found. A power line turns East & West just South of the apparent corner position. A 1" pipe and a 1 1/4" pipe was found South of the power line and South of the calculated corner position.

Corner was re-established by single proportionate measurement and on line between opposite section corners.


Research on file with the Ontonagon County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 1/2"x30" aluminum pipe with a 3 1/4" cap stamped to read: County Remonumentation, 1/4, T48N, T47N, R40W, 1996, P.S. 17610. I established 3 bearing trees and two reference objects.

Centerline REA Power line South 27.70'
3 1/2" Oak S15°-15'-12"E 54.84' - 6" Aspen N67°-09'-01"E 29.99'
8" Aspen N29°-33'-31"W 19.82' - Steel Sign Post North 0.59'

PEER GROUP APPROVED
Earl W. Applekamp
COUNTY REPRESENTATIVE
07-08-96



Signed by Earl W. Applekamp
Surveyor's Michigan License No. 17610

Date June 6, 1996