

**SURVEY & REMONUMENTATION**

DEC 16 1996

**COMMISSION**

JUDITH D. ROEHM  
 Ontonagon County  
 LC 4/ 48 JEM Fee: 9.00  
 Page 1 of 1

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T48N R 40W	H-9
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

1/4 Corner common to Sections 22 & 27, T48N R40W.

I, Earl W. Applekamp, in a field survey on April 24, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by J. Wells Burt, U.S. Deputy Surveyor, May 1851. Set Wood Post.

ORIGINAL BEARING TREES:

Black Ash 8" S80°W 33 links  
 Cedar 12" S37°W 21 links

PEER GROUP APPROVED  
*Earl W. Applekamp*  
 COUNTY REPRESENTATIVE 05-07-96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. At the corner position I found a 1/2" iron pin in a monument box near the centerline of Highway M-28. A County Road runs North from this point. The location was checked using single proportionate measurement between opposite section corners. It was within an inch of being at that location. I accepted the 1/2" iron pin as being the true location of the corner.

Research on file with the Ontonagon County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position is a 1/2" Iron Pin in a monument box near the centerline of Highway M-28. I established two reference monuments which are 2 1/2" X 30" aluminum pipe with a 3 1/4" cap stamped to read: County Remonumentation, 1/4, S22, S27, T48N R40W; R.M., 1996, P.S. 17610. I also established two other reference objects.

REF. MON. N45°-29'-16"W 104.55' REA P. Pole N23°-45'-29"W 111.33'  
 REF. MON. N29°-06'-06"E 77.72' Fence Post S07°-24'-09"E 61.81'



Signed by Earl W. Applekamp Date April 30, 1996  
 Surveyor's Michigan License No. 17610