

DEC 1 6 1996

COMMISSION

JUDITH D. ROEHM
Ontonagon County
LC 4/ 93 JEM Fee: 9.00
Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ONTONAGON (County)	Located In:	Corner Code #
1. Public Land Survey	T47N R 40W T48N R 40W	H-1 H-13
2. Property Controlling in Section	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1/4 Corner common to Sections 3 & 34, T47N & T48N, R40.

I, Earl W. Applekamp, in a field survey on May 22, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by John Burt, U.S. Deputy Surveyor, July 13, 1850. Set Maple Post.

ORIGINAL BEARING TREES:

Cedar 14" N76°E 11 links
Cedar 18" N40°W 41 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Corner was re-established by single proportionate measurement between opposite section corners East & West and using the existing old fence line to set the latitude.

PEER GROUP APPROVED
Earl W. Applekamp
COUNTY REPRESENTATIVE
07-08-96

Research on file with the Ontonagon County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

at the corner position I set a 2 1/2"x30" aluminum pipe with a 3 1/2" cap stamped to read: County Remonumentation, 1/4, T47N, T48N, R40W, 1996, P.S. 17610. I established three bearing trees and one reference object.

6" Oak N70°W 54.88' 4" Spruce S16°E 36.92'
12" Oak N13°E 53.13' Steel Sisp Post North 1.63'



Signed by Earl W. Applekamp
Surveyor's Michigan License No. 17610

Date June 20, 1996

S