

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

JUDITH D. ROEHM
 Ontonagon County
 LC 3/309 JEM Fee: 9.00
 09/22/95
 08:37
 Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
ONTONAGON
 (County)

Located In: Corner Code #

- | | | |
|------------------------------------|-------------------|-------|
| 1. Public Land Survey | T 48 R 40 | I-10 |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

1/4 Corner Sections 26 & 27, T.48N, R.40W.

I, Earl W. Applekamp, in a field survey on April 08, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Wills Burt, U.S. Duputy Surveyor, May 1951. A fir 4" diameter was at corner.

Original Bearing Trees:

Maple 5"	S46°E	8 Links	(5.28 feet)
Fir 5"	N43°W	16 Links	(10.56 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

The corner was established and used for the Plat of Hanson Heights prepared by E.W. Applekamp P.S. and recorded in 1973. The corner is the SE corner of this Plat. The corner was marked by a 1" Drill Steel. This corner was used for several surveys in the area over the last 20 plus years.



PEER GROUP APPROVED

Earl W. Applekamp
 COUNTY REPRESENTATIVE 4-20-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8" iron rod with a 3 1/4" aluminum cap, insulated from the iron with a plastic insert. The cap is set flush with the top of the blacktop. The cap is stamped to read: COUNTY REMONUMENTATION, 1/4, S.26, S.27, T48N R40W, 1995, P.S. 17610. I established the following bearing trees and reference objects.

12" Spruce	N48°W	41.79 feet	Power Pole	S12°E	30.00 Feet
20" W. Pine	S23°W	36.84 feet	Steel Sign Post	South	28.09 Feet

Signed by Earl W. Applekamp Date May 29, 1995
 Surveyor's Michigan License No. 17610

309