JUDITH D. ROEHM Ontonason County LC 4/ 95 JEM 07/11/96

08:46

Fee: 9.00 Page 1 of 1

DEC 1 6 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

tar vanadi.

-or comers in		
ONTONAGON	Located In:	Corner Code #
(County)	•	
I. Public Land Survey	T <u>48N</u> R_ TR_ TR	40W I-12
2. Property Controlling in Section 3. Miscellaneous	TR TR S TR S TR S TR	

Register of Deeds Stamp & File Number


4. Lot No,	Recorded Plat
5. Private Claims _	

T___R_

 $\frac{1}{4}$ Corner common to Sections 34 & 35, T48N R40W.

I, Earl W. Applekamp, in a field survey on May 16, 19, 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 comers, all in the same town and range, may be recorded on this certificate.



A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Wells Burt, U.S. Deputy Surveyor, May 29, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

Property in Sec.

White Birch 10" S35°E 11 links Cedar 6" N46°E 12 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Corner will be re-established by single proportionate measurement between opposite section corners North & South.

PEER GROUP APPROVED

Lack W Caplifacing

COUNTY BEFFESHITATIVE

07-08-96

Research on file with the Ontonagon County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner

At the corner position I set a $2\frac{1}{2}$ "X30" aluminum pipe with a $3\frac{1}{4}$ " cap stamped to read: County Remonumentation, $\frac{1}{4}$, T48N R40W, S34, S35, 1996, P.S. 17610. I established three bearing trees and one reference object.

EARL W.

APPLEKAMP
PROFESSIONAL
NO.
17610
POFESSIONAL
APPLESSIONAL
APP

10" Maple S27°-50'-16"W 49.90' - 11" Oak S54°-44'-54"E 20.31' 6" Maple N25°-14'-08"W 8.01' - Steel Sign Post West 1.07'

Signed by Sail W	applekaus	
Surveyor's Michigan License No.	17610	

Date June 8, 1996