

**SURVEY &
REMONUMENTATION**

DEC 16 1996

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

JUDITH D. ROEHN
Ontonagon County
LC 4/ 97 JEM Fees 9.00
Page 1 of 1

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>40W</u>	<u>J-7</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

$\frac{1}{4}$ Corner common to Section 14 & 23, T48N R40W.

I, Earl W. Applekamp, in a field survey on June 14, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Wells Burt, U.S. Deputy Surveyor, May 25, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

W. Pine 9" N73°W 12 links
Spruce 6" N73°E 13 links

PEER GROUP APPROVED
Earl W. Applekamp
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

07-08-96

No original evidence was found. At the corner position I found a $\frac{1}{2}$ " iron pin which was set by E.W. Applekamp No. 17610 in 1985 for a section subdivision. This pin is near the center of a gravel road and in line with a fence and woods/field line running North & South. The corner was set at this position as it is the only logical position for the corner.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"x24" rebar with a 3/4" stamped cap 5" below the top of a gravel road. I established one reference monument, a 2 1/2"x30" aluminum pipe with a 3/4" cap stamped to read: County Remonumentation, $\frac{1}{4}$, T48N R40W, S14, S23, 1996, P.S. 17610. I established 3 other bearing objects.

REF. MON. S37°-15'-08"W 46.30' - 7" Spruce N04°-00'-44"E 63.21'
5" Oak S56°-34'-29"W 59.53' - P. Pole N69°-58'-41"E 96.06'



Signed by *Earl W. Applekamp*
Surveyor's Michigan License No. 17610

Date July 3, 1996