

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48NR 40W</u>	<u>J-9</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

$\frac{1}{4}$ Corner common to Sections 23 & 26, T48N R40W.

I, Earl W. Applekamp in a field survey on April 23, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
 Original corner established by J. Wells Burt, U.S. Deputy Surveyor in May 1851. Set Wood Post.

ORIGINAL BEARING TREES:
 Aspen 8" East 8 links
 Spruce 6" S10°E 5 links

PEER GROUP APPROVED
Earl W. Applekamp 5-07-96
 COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 No original evidence was found. Recent road construction altered the ground in the area. Corner was re-established by single proportionate measurement between opposite section corners. This location is in agreement with 3 metes & bounds surveys using the corner as the P.O.B. Corner location is in conformance with the original field notes.

Research on file with the Ontonagon County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 At the corner position I set a P.K. nail with a 1" washer in the blacktop roadway of Highway M-28. I established two reference monuments which are 2 1/2" X 30" aluminum pipe with a 3 1/4" cap stamped to read: County Remonumentation, 1/4, S23, S26, T48N R40W, R.M., 1996, P.S. 17610. I also established two bearing trees.

REF. MON.	S07°-50'-13"E	73.64'	11" Red Pine	N30°-26'-54"W	66.64'
REF. MON.	N14°-22'-54"E	114.26'	12" Red Pine	S40°-23'-42"W	91.79'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date April 30, 1996