

**SURVEY &
REMONUMENTATION**

MAY 05 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

JUDITH D. ROEHM
Ontonagon County
LC 4/ 68 JEM Fees 9.00
06/10/96
15:38
Page 1 of 1

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T48N R40W	K-10
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1/4 Corner common to Sections 25 & 26, T48N R40W.

I, Earl W. Applekamp, in a field survey on May 11, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	19		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Wells Burt, U.S. Deputy Surveyor, May 26, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

White Pine 24" N32°E 17 links
Sugar 10" S15°W 14 links

Earl W. Applekamp
COUNTY _____
06-06-96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence remains. At the corner position there is a fence running East & West and a blacktop road running North & South. Corner will be re-established at this location. This position is in conformance with the original distance to the corner North but is about 35 feet short of the corner to the South. Research on file explains this in detail.

Research on file with the Ontonagon Co. Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"x7" Rebar with a 3 1/4" cap set 2" below top of blacktop, stamped to read: County Remonumentation, 1/4, S25, S26, T48N R40W, 1996, P.S. 17610. I established one reference monument, a 2 1/2"x30" aluminum pipe with a stamped cap. I also established two bearing trees.

REF. MON. N54°-29'-52"E 44.26' 5" White Birch N31°-30'-57"E 73.62'
11" Soft Maple S76°-36'-15"W 113.28'



Signed by Earl W. Applekamp
Surveyor's Michigan License No. 17610

Date May 13, 1996