

SURVEY & REMONUMENTATION

DEC 16 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JUDITH D. ROEHM
Ontonagon County
LC 4/ 55 JEM Fees 9.00
05/09/96 14:25
Page 1 of 1

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48NR 40W</u>	<u>K-11</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner common to 25, 26, 35, & 36, T48N R40W.

I, Earl W. Applekamp, in a field survey on April 21, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original Corner established by J. Wells Burt, U.S. Deputy Surveyor, May 26, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

White Pine 22" N65°W 9 links
White Pine 18" S77°E 37 links

PEER GROUP APPROVED
Earl W. Applekamp
COUNTY REPRESENTATIVE
05-07-96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. At the apparent corner there is a 1" Drill Steel. This object is identified in several surveys in the area. It is located at the intersection of two county roads. The location is consistent with occupied lines in the area. I accepted the location as being the true location and monumented it as described in "C" below.

Research on file with the Ontonagon County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

AT the corner position I left the 1" Drill Steel as the corner marker which is 2" below top of a blacktop road. I established two reference monuments, each a 2 1/2" X 30" aluminum pipe with a 3 1/4" cap stamped to read: County Remonumentation, R.M., S25, S26, S35, & S36, 1996, P.S. 17610. I established two other reference objects.

REF. MON. S49°-22'-46"E 46.53' 3" White Pine S44°-26'-52"W 69.87'
REF. MON. N47°-29'-41"W 59.15' REA P. Pole S22°-00'-34"W 89.50'



Signed by Earl W. Applekamp
Surveyor's Michigan License No. 17610

Date May 3, 1996