

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ONTONAGON (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 40W	L-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

**SURVEY &
 REMONUMENTATION**

MAY 22 1997

COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

1/4 Corner common to Sections 25 & 36, T48N R40W.

I, Earl W. Applekamp, in a field survey on August 12 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Wells Burt, U.S. Deputy Surveyor, May 27, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

W. Pine 24" S76°E 19.80 feet
 W. Pine 16" N70°W 18.48 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. At the apparent corner I found a fence running in all four directions and a 1" Drill Steel set at this location. This Drill Steel was set by E.W. Applekamp, P.S. 17610 in July 1982 to describe 8 parcels of land in the West 1/2 of Section 36. The land occupied in all four directions from this corner position. I accepted the location of the 1" Drill Steel as being the true location of the corner.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 1/2"x30" aluminum pipe with a 3 1/4" stamped cap over the 1" Drill Steel. Cap is stamped to read: County Remonumentation, T48N R40W, 1/4, S25, S36, 1996, P.S. 17610, I established three bearing trees and one other reference object.

9" W. Pine S64°-38'-57"W 37.64' - 6" Maple N83°-41'-28"E 51.06'
 14" Maple N07°-20'-28"W 47.87' - Steel sign post South 1.20'

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE
 9-12-96



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date August 22, 1996