

SURVEY & REMONUMENTATION

DEC 16 1996

COMMISSION

JUDITH D. ROEHM
Ontonagon County
LC 4/ 57 JEM Fee: 9.00
Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T48N R 39W	A-10
	T48N R 40W	M-10
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1/4 Corner common to Sections 25 & 30, T48N R39-40W.

I, Earl W. Applekamp, in a field survey on April 22, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by J. Wells Burt, U.S. Deputy Surveyor on June 1851.

ORIGINAL BEARING TREES:

Cedar 16" N49°E 51 links
Sugar 8" N56°W 22 links

PEER GROUP APPROVED
Earl W. Applekamp 5-07-96
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence found. A barb wire fence runs West from the corner location.

Corner was established by single proportionate measurement between the Section Corner North and South.

Research on file with the Ontonagon County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"x21" iron pin with a 3/4" cap stamped to read: County Remonumentation, 1/4, S25, S30, T48N R39W-R40W, 1996, P.S. 17610. I established one reference monument, a 2 1/2"x30" aluminum pipe with a 3/4" stamped cap and three reference objects.

REF. MON.	N73°-37'-24"W	47.75'	5" Aspen	N54°-31'-55"E	53.95'
REA P. Pole	N85°-38'-50"W	33.01'	6" Maple	S53°-27'-45"E	76.26'



Signed by Earl W. Applekamp
Surveyor's Michigan License No. 17610

Date April 30, 1996