

SURVEY & REMONUMENTATION

MAY 05 1997

COMMISSION

JUDITH D. ROEHM
 Ontonagon County
 LC 4/ 58 JEM Fee: 9.00
 05/09/96 14:28
 Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>48</u> N R <u>39</u> W	<u>A-11</u>
	T <u>48</u> N R <u>40</u> W	<u>M-11</u>
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section corner common to Sections 30 & 31, T48N R39W and Sections 25 & 36, T48N R40W.

I, Earl W. Applekamp, in a field survey on April 18, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Artemas Curtis, U.S. Deputy Surveyor, September 1851. Set Hemlock Post.

ORIGINAL BEARING TREES:

White Pine 36" S32°E 24 links
 White Birch 20" N44°W 31 links

PEER GROUP APPROVED
Earl W. Applekamp 5-07-96
 COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Occupied land with old fence (50 plus years) were checked a mile South and ½ mile North. These agree with original calls. Measuring East and West one mile agree with original calls. Corner was established at the intersection of the centerline of the blacktop road and the occupied line running West. This is a 20± North of the centerline of a gravel road running East.

Research is on file with the Ontonagon County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"X24" rebar with a 3/4" aluminum cap (insulated from the steel), 2" below top of blacktop. Cap is stamped to read: County Remonumentation, S25, S30, S31, S36, T48N R40W & R39W, 1996, P.S. 17610. I established one reference monument, a 2 1/2"X30" aluminum pipe with a 3/4" stamped cap and three other reference objects.

REF. MON. S57°-24'-28"W 36.30' REA P. Pole N04°-23'-44"W 310.58'
 REA P. Pole N89°-52'-14"E 359.47' REA P. Pole N88°-35'-12"W 24.33'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date April 30, 1996