

APR 29 1996

COMMISSION

JUDITH D. ROEHM  
 Ontonagon County  
 LC 3/302 JEM Fee: 9.00  
 08/09/95  
 14:25  
 Page 1 of 1

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ONTONAGON  
 (County)

Located In:

Corner Code #

|                                      |      |      |            |
|--------------------------------------|------|------|------------|
| 1. Public Land Survey                | T48  | R 41 | <u>B-1</u> |
|                                      | T 49 | R 41 | B-13       |
|                                      | T    | R    |            |
|                                      | T    | R    |            |
| 2. Property Controlling in Section   | S    | T    | R          |
|                                      | S    | T    | R          |
| 3. Miscellaneous Property in Section | S    | T    | R          |
|                                      | S    | T    | R          |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner common to Section 6 & Section 31, T48N & T49N, R41W

I, Earl W. Applekamp, in a field survey on July 10, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Willam A. Burt, U.S. Deputy Surveyor, July 1857. Set Elm Post.

ORIGINAL BEARING TREES:

Spruce 14" N20°E 34 Links (22.44 feet)  
 Sugar 6" N44°W 46 Links (30.36 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner was found. At the corner location there are old fence lines running in all 4 directions. There is a hay field NE of this corner location. This corner is consistent with the original field note calls. I set a monument described in "C" below. This corner is one of 29 corners in 6 sections remonumented under the County Remonumentation Program. Research is on file with the Ontonagon County Remonumentation Program Representative.

PEER GROUP APPROVED

Earl W. Applekamp  
 COUNTY REPRESENTATIVE  
 8-08-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 $\frac{1}{2}$ "x30" aluminum pipe with a 3 $\frac{1}{4}$ " cap stamped to read: COUNTY REMONUMENTATION,  $\frac{1}{4}$ , S6, S31, T48N & T49N, R41W, 1995, P.S. 17610. I established the following bearing trees and reference objects.

16" Spruce N19°W 31.95 feet 5" Aspen N89°E 23.45 feet  
 5" Spruce N48° 55.30 feet Steel sign post 1.72 feet



Signed by Earl W. Applekamp

Date July 12, 1995

Surveyor's Michigan License No. 17610

