

APR 29 1996

JUDITH D. ROEHM
 Ontonagon County
 LC 3/300 JEM Fee: 9.00
 08/09/95
 14:20
 Page 1 of 1

COMMISSION LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in ONTONAGON Located In: _____ Corner Code # _____
 (County)

- | | | |
|--------------------------------------|-------------------------|-------|
| 1. Public Land Survey | T 48 R 41 | B-5 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

$\frac{1}{4}$ Corner common to Sections 7 & 18, T48N R41W

I, Earl W. Applekamp, in a field survey on May 23, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5	●											
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Wills Burt U.S. Deputy Surveyor, June 1851. Set post.

- Aspen 16" S55°E 7 Links (4.62')
 W. Birch 8" S34°W 12 Links (7.92')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of the corner was found. Corner was re-established by single proportionate measurement on a line between the SE & SW corner of Section 7. This corner was one of the corners re-monumented in a block of 6 Sections in which all original corners were re-established.

Research on file with the County Remonumentation Program Representative.

PEER GROUP APPROVED

Earl W. Applekamp
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 3/4"x18" aluminum rod with a 3/4" cap 6" below the top of gravel on a country road stamped to read: COUNTY REMONUMENTATION, $\frac{1}{4}$, S7, S18, T48N R41W, 1995, P.S. 17610. I established the following witness trees and witness monument.

- | | |
|--------------------------------|---------------------------------|
| 5" Aspen N23°W 40.28 feet | 11" Aspen N61°E 75.39 feet |
| 3" Apple tree S01°E 37.35 feet | Witness corner N01°E 26.54 feet |



Signed by *Earl W. Applekamp*
 Surveyor's Michigan License No. 17610

Date June 10, 1995