

APR 29 1995

COMMISSION

JUDITH D. ROEHM  
Ontonagon County  
LC 3/297 JEM Fee: 9.00  
08/09/95  
14:04  
Page 1 of 1

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in ONTONAGON Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

- |                                       |   |    |   |    |     |
|---------------------------------------|---|----|---|----|-----|
| 1. Public Land Survey                 | T | 48 | R | 41 | C-3 |
|                                       | T |    | R |    |     |
|                                       | T |    | R |    |     |
|                                       | T |    | R |    |     |
| 2. Property Controlling in Section    | S |    | T | R  |     |
|                                       | S |    | T | R  |     |
| 3. Miscellaneous                      | S |    | T | R  |     |
| Property in Section                   | S |    | T | R  |     |
| 4. Lot No. _____, Recorded Plat _____ |   |    |   |    |     |
| 5. Private Claims _____               |   |    |   |    |     |

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3		●										
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Section corner common to 5, 6, 7 & 8, T48N R41W  
I, Earl W. Applekamp, in a field survey on May 22, 19 95  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Wills Burt U.S. Deputy Surveyor, June 1851.  
Set Post.

Original Bearing Trees:

W. Pine	20"	S20°E	29 Links	(19.14 Feet)
Cedar	20"	N42°E	19 Links	(12.54 Feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Iron Pin at intersection of 2 county roads. Corner was used for a survey in 1972. The location of the marker was consistent with the original field notes. I accepted the location. This corner was one of the corners re-monumented in a Block of 6 Sections in which all corners were re-established.

Research on file with the County Remonumentation Program Representative.

PEER GROUP APPROVED  
Earl W. Applekamp 8-08-95  
COUNTY REPRESENTATIVE



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 3/4"x 18" aluminum rod with a 3/4" cap, 7" below top of gravel surface. Cap is stamped to read: COUNTY REMONUMENTATION, S5, S6, S7, S8, T48N R41W, 1995, P.S. 17610. I established the following witness objects to relocate the actual corner.

Witness Monument	S50°W	44.58 Feet	South end CMP	S40°E	28.65 Feet
North end 18" CMP	N59°E	32.85 Feet	Power Pole	S26°E	44.83 Feet

Signed by Earl W. Applekamp Date June 14, 1995  
Surveyor's Michigan License No. 17610