

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

JUDITH D. ROEHM
 Ontonagon County
 LC 3/ 293 JEM Fee: 9.00
 08/09/95
 13:51
 Page 1 of 1

For corners in
ONTONAGON
 (County)

Located In:

Corner Code #

- | | | | |
|--------------------------------------|------|------|-----|
| 1. Public Land Survey | T 48 | R 41 | C-5 |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Section | S | T | R |
| | S | T | R |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner common to Sections 7, 8, 17 & 18, T48n R41W

I, Earl W. Applekamp, in a field survey on June 02, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Wills Burt, U.S. Deputy Surveyor, June 1851.
 Set Post

No original bearing trees noted on original Government field notes.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner or bearing trees were found. Corner position is in the intersection of two Township roads. A 1" pipe was at the position and was used for two surveys in the area in 1971 and 1972. Corner was one of the corners re-monumented in a Block of 6 Sections in which all original corners were re-established.

Research on file with County Remonumentation Program Representative.

PEER GROUP APPROVED
Earl W. Applekamp 8-08-95
COUNTY REPRESENTATIVE



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 3/4"x18" aluminum rod with a 3 1/4" cap stamped to read: COUNTY REMONUMENTATION, S7, S8, S17, S18, T48N R41W, 1995, P.S. 17610. Cap is near the centerline of a blacktop road and 1" below the surface. I established the following witnesses:

Utility Pole S66°W 72.84 Feet - Corner Fence Post S58°E 44.93 Feet

3" Red Pine S28°W 52.06 Feet - Witness Corner N41°W 41.88 Feet

Signed by Earl W. Applekamp Date June 18, 1995
 Surveyor's Michigan License No. 17610