

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ONTONAGON (County)	Located In:	Corner Code #
1. Public Land Survey	T48NR 41W	C-6
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

REMO

OCT 30 1997

COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

1/4 Corner common to Sections 17 & 18, T48N R41W.

I, Earl W. Applekamp, in a field survey on Sept. 17, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Wells Burt, U.S. Deputy Surveyor, June 11, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

16" Cedar North 3.96 feet
 12" Cedar S20°E 9.90 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence remains. Apparent corner position is in blacktop County Road running North & South. I re-established the corner by single proportionate measurement and in the center-line of the blacktop road. An occupation fence line runs East from the re-established corner position.

Research on file with the Ontonagon County Remonumentation Program Representative.

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE

9-17-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"x8" rebar with a stamped cap 2" below top of blacktop. I established a reference monument, a 2 1/2"x30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T48N R41W, R.M., 1/4, S17, S18, 1997, P.S. 17610. I also established three other bearing objects.

REF. MON. East 37.44' - 6" Aspen N54°W 49.99'
 9" Aspen S43°W 58.03' - P. Pole N26°E 71.07'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date September 17, 1997