

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T48N R41W	C-8
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

REMONUMENTATION

OCT 9 01997

COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

$\frac{1}{4}$ Corner common to Sections 19 & 20, T48N R41W.

I, Earl W. Applekamp, in a field survey on August 11 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Wells Burt, U.S. Deputy Surveyor, June 12, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

6" Spruce S42°E 3.96 feet
 16" Y. Birch N44°E 21.78 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Apparent corner position is in a blacktop county road running North & South. Corner was re-re-established by single proportionate measure between opposite section corners North & South and in the centerline of the blacktop road.

Research on file with the Ontonagon County Remonumentation Program Representative.

PEER GROUP APPROVED

Earl W. Applekamp
 COUNTY REPRESENTATIVE 9-17-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"X12" rebar with a 3" stamped cap, 3" below top of the blacktop road. I established a reference monument, a 2 1/2"X30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T 48N R41W, R.M., $\frac{1}{4}$, S19, S20, 1997, P.S. 17610. I also established three other reference objects.

REF MON S57°-37'-35"W 44.32' - Power Pole N18°-02'-28"E 80.08'
 8" Aspen N68°-19'-11"W 35.62' - 6" Aspen S46°-12'-11"E 93.11'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date September 15, 1997