

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T48N R41W	C-10
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

**SURVEY &
REMONUMENTATION**

MAR 23 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

¼ Corner common to Sections 29 & 30, T48N R41W.

I, Earl W. Applekamp, in a field survey on Aug. 19, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Wells Burt, U.S. Deputy Surveyor, June 12, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

16" Cedar S08°W 7.26 feet
 15" Fir N30°W 14.52 feet

DEED GROUP APPROVED
Earl W. Applekamp
 COUNTY REGISTRAR
 8-24-99

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


No original evidence was found. A dirt road runs North & South through this corner. This road has been in existence for the past 50 years. A yellow tag marked the approximate corner. A blue paint line runs West from this position. I re-established the corner by proportionate measure between corners North & South and in the center-line of the well used dirt road.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"X12" rebar with a 3" stamped cap 10" below top of the dirt road. The cap is stamped to read: County Remonumentation, T48N, R41W, S29, S30, ¼, 1999, P.S. 17610. I established a reference monument, a 2½"X30" split base aluminum pipe with a 3" cap stamped as above adding R.M. I also established three bearing trees.

REF. MON. N89°W 29.74' - Nail in 4" Spruce N75E 54.36'
 Nail in 6" Aspen S38°W 72.13' - Nail in 7" Aspen S41°E 44.42'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date August 23, 1999